

KLJ Corporate Office



Bismarck, North Dakota

Year Completed: 2013

Electrical Construction: \$1,360,000

Project Manager: Paul Soderquist

Project Foreman: Galen Weiss

Architect: JLG Architects

General Contractor: Northwest Contracting

KLJ's new corporate office was a 3-story, 80,000 square foot new construction project in the north end of Bismarck and mostly consisted of offices, cubicles and conference rooms.

Bergstrom Electric worked as a sub to Northwest Contracting and started in June of 2012, installing temporary power and doing some site work. Crews installed a standard 480 volt primary service with a step down to 240 transformers. Approximately 200,000 feet of wire and about 1500 lights were also installed.

Construction was complete in November of 2013 and took over 13,000 man-hours.



**BERGSTROM
ELECTRIC, INC.**
"Employee Owned"
Where Quality & Customers Matter